BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Maintenance of community property parks in Sahakaranagara E Block in Ward No.07

Work Order No: EE (Project)/Ynk Zone/WO/ 18/2020-21 Dt:- 13/05/2020

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. U RAMESH	
				In figures	In words
1	42.75	KSRRB 300-1. Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications	Cum	144.63	Rupees One Hundred Forty Four And Paise Sixty Three Only
2	4.27	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification	Cum	5676.36	Rupees Five Thousand Six Hundred Seventy Six And Paise Thirty Six Only
3	18.90	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	5113.40	Rupees Five Thousand One Hundred Thirteen And Paise Forty Only
4	5.40	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications	Cum	6100.25	Rupees Six Thousand One Hundred And Paise Twenty Five Only
5	60.00	KSRB 5-14.1 : Providing and constructing load bearing wall with solid concrete blocks of size 400x100x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work.	Sqm	902.30	Rupees Nine Hundred Two And Paise Thirty Only
6	60.00	KSRB 15.3.13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 114 / Item No. 15.21	Sqm	218.78	Rupees Two Hundred Eighteen And Paise Seventy Eight Only
7	60.00	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Sqm	100.89	Rupees One Hundred And Paise Eighty Nine Only
8		GST @ 12%			

13/5/2020

U. Ramesh
Contractor

Executive Engineer
Project Division
Yelahanka Zone